

ADDENDUM 01 NARRATIVE

2 page(s) | 1

project number ARA007
event date 06-12-2017

project name Cinergy Amarillo
venue Via E-Mail

> distribution

All Bidders	Various	e-mail
Jeff Benson	Cinergy	e-mail
Kathi Gillman	Cinergy	e-mail
Colin Edwards	Hunt Joiner	e-mail
Sam Patton	Envirodesign	e-mail
Andrew Mellon	Maverick Engineering	e-mail
Mike Voegtle	5G Studio	e-mail

> addendum instructions

The sheets issued in this addendum supersede contract documents previously issued for bid. Replace all sheets indicated in your original issue for bid and provide pricing on the Bid Form. Indicate receipt of this addendum on your Bid Form.

> narrative of revisions

ARCHITECTURAL SHEETS

- A00.00** Coordinate sheet index and current issue with current revisions.
- A10.20** Added second man gate from patio for egress.
- A20.01a** Add wall tags behind Auditoriums 7-10.
- A20.02a** Add Keynote A2-23.
- A20.02b** Add Keynote A2-23.
- A20.30** Add Keynote A2-05
- A20.40** Removed one seat from Auditoriums 8-10.
- A21.00** Detail 13 – Add product data and clarify responsibilities.
- A22.00** Detail 17 – Add note to install continuous black caulking. Added notes to clarify location and height of wall support.
- A22.01** Detail 15 – Add riser closure framing.
- A22.02** Detail 1 – Revise jamb detail callout at interior storefronts. Add interior storefront header callouts.
- A20.01d** Keynote A2-02 - Add note to submit product data to fire marshal for review prior to installation. Added wall tags at sales offices. Change door 164 to 6'-0".
- A40.00** Change door 164 to 6'-0". Add Detail 9 – Interior Storefront Header.
- A50.00** Keynote A5-13 - Add note to install address signage.
- A61.01** Detail 4 – Add size of weep. Add continuous sealant at back edge of blocking. Add note to slope blocking.
- A70.01d** Detail 3 – Add Game floor pattern.
- A70.02b** Add Keynote A7-10 in Auditorium 01.

ADDENDUM 01 NARRATIVE

2 page(s) | 2

project number ARA007
event date 06-12-2017

project name Cinergy Amarillo
venue Via E-Mail

A90.10 Detail 3 – Revise pattern for Epic flooring.

STRUCTURAL SHEETS

Title block has been revised on all sheets.

- S1** Posts added for the support of the bathroom sinks
- S3** Detail 11/S3 revised to reduce the footing thickness to a thickened slab section.
- S3.1** Thickened slabs removed and geofoam shown for all risers and ramp slabs. Notes added for steel beam enclosures on the riser framing sections.
- S3.3** Detail 8/S3.3 added for the bathroom sink supports.

MEP SHEETS

See attached narrative dated 6-8-17.

If there is any exception to the Memo, please notify 5Gstudio within 5 days.
If no exception is noted, the Memo will stand as written.

end of narrative

Cinergy Amarillo

MEP, Delta 1, Addendum #1

Thursday, June 08, 2017

The following is a summary of all the changes in the documents. The pricing is to be submitted on a per line item basis (to match this write-up) with total cost, material cost, labor cost with backup.

DWG #	Description of Revisions to Drawings	Cinergy Request	A/E coordination	Clarification	Contractor requested change	Sub-Contractor Cost		
						Labor	Material	Total
E3.1A	1. Add (18) 120V circuits for games	X						
E7.1	1. Increased feed to size to panel 1LB2	X						
E7.2	1. Upsized breaker in panel 1LB serving 1LB2 from 100 to 150 amp	X						
3					<i>Sub-Total:</i>			
sheets					<i>GC Profit:</i>			
					<i>GC Change Order Total</i>			